



101 LOBBY  
500 SF

**102 CONFERENCE**  
500 SF

**103 OFFICE**  
500 SF

**104 OFFICE**  
500 SF

SK-1

**105 BREAK ROOM**  
500 SF

**108 OFFICE**  
500 SF

106 RESTROOM M  
250 SF

WC-1 WC-1  
107 RESTROOM W  
250 SF

109 IT / STORAGE  
500 SF

200 WAREHOUSE  
8,000 SF

HB-1

| TAG   | DESCRIPTION                         | QTY |
|-------|-------------------------------------|-----|
| WC-1  | WATER CLOSET, FLOOR MOUNT, 1.28 GPF | 4   |
| UR-1  | URINAL, WALL HUNG, 0.125 GPF        | 1   |
| LAV-1 | LAVATORY, WALL HUNG                 | 4   |
| SK-1  | BREAK ROOM SINK, DOUBLE BOWL        | 1   |
| MS-1  | MOP SINK                            | 1   |
| EW-1  | ELECTRIC WATER COOLER, BI-LEVEL     | 1   |
| WH-1  | ELECTRIC WATER HEATER, 40 GAL       | 1   |
| HB-1  | HOSE BIBB                           | 4   |



| AREA               | HAZARD         | SF/HEAD | HEADS |
|--------------------|----------------|---------|-------|
| OFFICE 4,000 SF    | LIGHT          | 200     | 20    |
| WAREHOUSE 8,000 SF | ORDINARY GRP 2 | 130     | 62    |

1. DOMESTIC WATER: 2" SERVICE WITH RPZ BACKFLOW; COPPER TYPE L ABOVE GRADE, PEX-A PERMITTED IN WALLS.
2. SANITARY: PVC SCH 40 UNDERGROUND, CAST IRON ABOVE GRADE; APPROX. 420 LF TOTAL.
3. GAS: 1-1/2" TO UH-1/UH-2 AND 3/4" TO WH-1; METER BY UTILITY.
4. ROOF DRAINS (4) AND OVERFLOWS (4) WITH 6" LEADERS TO STORM; SEE CIVIL FOR SITE STORM.
5. SPRINKLER: WET PIPE, 6" RISER, FDC AT NORTH WALL; FLOW TEST 09/2026 TO BE PROVIDED BY OWNER.

**BLACKLAND COMMERCIAL BUILDERS (SYNTHETIC C)**  
PRAIRIE CREEK OFFICE/WAREHOUSE — BUILDING 2

SHEET TITLE

**PLUMBING PLAN & FIXTURE SCHEDULE**

SCALE: 1/8" = 1'-0"      DATE: 09/12/2026

REV: 2 ADDENDUM 1: 09/19/2026

SHEET NUMBER **P-101**