

PROJECT MANUAL — PRAIRIE CREEK OFFICE/WAREHOUSE — BUILDING 2

BLACKLAND COMMERCIAL BUILDERS (SYNTHETIC DEMO). Issued for bid 09/12/2026.
SYNTHETIC DEMO DATA — not a real project.

TABLE OF CONTENTS

- 00 11 13 — ADVERTISEMENT FOR BIDS
- 00 21 13 — INSTRUCTIONS TO BIDDERS
- 00 41 00 — BID FORM
- 01 10 00 — SUMMARY
- 01 21 00 — ALLOWANCES
- 01 22 00 — UNIT PRICES
- 01 23 00 — ALTERNATES
- 01 45 00 — QUALITY CONTROL
- 01 50 00 — TEMPORARY FACILITIES AND CONTROLS
- 03 30 00 — CAST-IN-PLACE CONCRETE
- 04 22 00 — CONCRETE UNIT MASONRY
- 05 12 00 — STRUCTURAL STEEL FRAMING
- 07 54 00 — THERMOPLASTIC MEMBRANE ROOFING
- 08 11 13 — HOLLOW METAL DOORS AND FRAMES
- 08 41 13 — ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
- 08 71 00 — DOOR HARDWARE
- 09 29 00 — GYPSUM BOARD
- 09 51 13 — ACOUSTICAL PANEL CEILINGS
- 09 65 00 — RESILIENT AND CARPET FLOORING
- 09 91 23 — INTERIOR PAINTING
- 21 13 13 — WET-PIPE SPRINKLER SYSTEMS
- 22 40 00 — PLUMBING FIXTURES
- 23 74 13 — PACKAGED ROOFTOP AIR-CONDITIONING UNITS
- 26 24 16 — PANELBOARDS
- 26 51 00 — INTERIOR LIGHTING
- 28 31 00 — FIRE DETECTION AND ALARM
- 31 23 00 — EXCAVATION AND FILL

SECTION 00 11 13 — ADVERTISEMENT FOR BIDS

Blackland Commercial Builders (synthetic demo) invites sealed bids for the Prairie Creek Office/Warehouse — Building 2, a 12,000 SF single-story office/warehouse in Plano, Texas.

Bids are due 09/26/2026 at 2:00 PM local time. A pre-bid site visit is scheduled for 09/16/2026 at 10:00 AM.

SECTION 00 21 13 — INSTRUCTIONS TO BIDDERS

Pre-bid requests for information (RFI) must be received in writing by 09/19/2026 at 5:00 PM; answers are issued by addendum to all bidders.

A bid bond of 5% of the base bid is required. Performance and payment bonds of 100% are required on award. Bids are valid for 60 days.

Contract form: AIA A101-2017 with A201-2017 General Conditions as amended by the Supplementary Conditions. Drawings and specifications are complementary; specifications govern in a direct conflict.

SECTION 00 41 00 — BID FORM

Base Bid: the complete work shown and specified, lump sum. Contract duration: 240 calendar days from Notice to Proceed. Liquidated damages: \$750 per calendar day.

Alternate No. 1 (ADD): epoxy floor coating in Warehouse 200 in lieu of sealed concrete. Alternate No. 2 (DEDUCT): delete brick veneer at office, paint CMU.

Unit Price No. 1: rock excavation, per cubic yard. Unit Price No. 2: select fill import, per cubic yard in place.

Acknowledge Addendum No. 1 dated 09/19/2026.

SECTION 01 10 00 — SUMMARY

The Work includes a 12,000 SF single-story building: 4,000 SF office with brick veneer on CMU, 8,000 SF warehouse with exposed painted CMU, steel joist and deck roof, TPO roofing, storefront entrance, complete MEP and fire sprinkler systems, and site work per the civil drawings (civil drawings are not included in this bid set; site work is by a separate contract).

Owner-furnished, contractor-installed: none. Not in contract: low-voltage cabling, furniture, warehouse racking, utility company charges.

SECTION 01 21 00 — ALLOWANCES

Include a cash allowance of \$25,000 for exterior and interior signage. Include a contingency allowance of \$15,000 for unforeseen conditions, to be used only with the Owner's written authorization.

SECTION 01 22 00 — UNIT PRICES

Unit Price No. 1: rock excavation, removal and disposal, per CY of bank measure. Unit Price No. 2: imported select fill, placed and compacted, per CY in place.

SECTION 01 23 00 — ALTERNATES

Alternate No. 1 (ADD): 100% solids epoxy floor coating, 20 mils, in Warehouse 200 (8,000 SF).

Alternate No. 2 (DEDUCT): delete modular brick veneer at office walls (west 100 LF and north 40 LF, 14 feet high); paint exposed CMU.

SECTION 01 45 00 — QUALITY CONTROL

Special inspections per IBC Chapter 17 for concrete, masonry and structural steel are paid by the Owner; the Contractor coordinates and provides access. Concrete testing: one set of cylinders per 100 CY or fraction per day.

SECTION 01 50 00 — TEMPORARY FACILITIES AND CONTROLS

Provide a 12x40 job trailer, temporary power and water (utility charges by Contractor), temporary chain-link fence around the site, two portable toilets, dumpsters, and a weekly cleaning. Provide a 6-foot construction fence for the duration.

SECTION 03 30 00 — CAST-IN-PLACE CONCRETE

Concrete f'c 4,000 psi at 28 days for all footings and slabs; 3,000 psi for fill. Air-entrained exterior flatwork. Reinforcing ASTM A615 Grade 60. Slab on grade: 4 inches in office on 10-mil vapor barrier with 6x6-W2.9xW2.9 WWM; 6 inches in warehouse with #4 at 18 inches each way. Finish: steel trowel; sealed concrete in the warehouse (base bid).

SECTION 04 22 00 — CONCRETE UNIT MASONRY

8-inch CMU ASTM C90, f'm 2,000 psi, Type S mortar, all cells grouted solid, #5 at 32 inches vertical, horizontal joint reinforcing at 16 inches. Modular brick veneer ASTM C216 Grade SW at the office with 1-inch air space, ties at 16 inches each way, and flashing/weepers.

SECTION 05 12 00 — STRUCTURAL STEEL FRAMING

W-shapes ASTM A992; HSS ASTM A500 Grade C; bolts ASTM A325 3/4 inch; shop primer. Connection design by the fabricator under a Texas PE seal. Steel joists SJI K-series with standard bridging; roof deck 1-1/2 inch Type B 22 gauge galvanized.

SECTION 07 54 00 — THERMOPLASTIC MEMBRANE ROOFING

60-mil TPO mechanically fastened over polyisocyanurate insulation, R-30 average, with tapered crickets and 1/2-inch cover board; 20-year NDL manufacturer's warranty. Prefinished aluminum coping 440 LF; four roof drains and four overflow drains.

SECTION 08 11 13 — HOLLOW METAL DOORS AND FRAMES

16-gauge hollow metal frames, 18-gauge doors, factory primed; 90-minute rated assembly at Door 110. Exterior doors insulated with thermal break frames.

SECTION 08 41 13 — ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

Clear anodized aluminum storefront, 1-inch insulated low-E glazing; entrance 101 pair 6'-0" x 7'-0" with panic hardware and closers. Windows W1 4'-0" x 5'-0" fixed, quantity 10.

SECTION 08 71 00 — DOOR HARDWARE

Hardware sets HW-1 through HW-4 per the schedule on A-601. Grade 1 locksets, Grade 1 closers, continuous hinges at the entrance pair, cylinders keyed to the Owner's system.

SECTION 09 29 00 — GYPSUM BOARD

5/8-inch Type X gypsum board on 3-5/8-inch 20-gauge metal studs at 16 inches on center; Level 4 finish in offices, Level 5 at the lobby feature wall; moisture-resistant board in restrooms; batt insulation in all partitions.

SECTION 09 51 13 — ACOUSTICAL PANEL CEILINGS

2x2 lay-in acoustical panels in a 15/16-inch grid, NRC 0.70, in all office rooms except restrooms (painted gypsum ceilings) and the warehouse (exposed).

SECTION 09 65 00 — RESILIENT AND CARPET FLOORING

Luxury vinyl tile in the lobby; carpet tile in offices, conference and break room; porcelain tile in restrooms with 6-inch tile base; 4-inch rubber base elsewhere.

SECTION 09 91 23 — INTERIOR PAINTING

Two finish coats over primer on all gypsum board; block filler plus two coats on exposed CMU in the warehouse; epoxy paint in restrooms.

SECTION 21 13 13 — WET-PIPE SPRINKLER SYSTEMS

Design-build wet-pipe system per NFPA 13: light hazard in the office and Ordinary Hazard Group 2 in the warehouse; 6-inch riser, FDC, backflow preventer; flow test data provided by the Owner. Fire pump is not anticipated; confirm with the flow test.

SECTION 22 40 00 — PLUMBING FIXTURES

Fixtures per the schedule on P-101; water closets 1.28 gpf floor mounted, urinal 0.125 gpf, wall-hung lavatories with sensor faucets, bi-level electric water cooler, 40-gallon electric water heater, mop sink, four hose bibbs.

SECTION 23 74 13 — PACKAGED ROOFTOP AIR-CONDITIONING UNITS

Two 7.5-ton packaged rooftop units with gas heat, economizers and programmable thermostats on 14-inch curbs; two 150 MBH gas unit heaters in the warehouse; two ceiling exhaust fans; galvanized ductwork per SMACNA; testing, adjusting and balancing per 23 05 93.

SECTION 26 24 16 — PANELBOARDS

400A main distribution panel 480Y/277V; 45 kVA transformer; 42-circuit 208Y/120V panelboard and 30-circuit 480Y/277V panelboard, copper bus, bolt-on breakers. Utility service by Oncor is not in contract.

SECTION 26 51 00 — INTERIOR LIGHTING

LED fixtures per the schedule on E-101 (40 troffers, 24 high bays, 8 wall packs, 6 exit signs) with occupancy sensors in offices and photocell/timeclock control for exterior lighting; 10-year fixture warranty.

SECTION 28 31 00 — FIRE DETECTION AND ALARM

Addressable fire alarm control panel, four pull stations, ten horn/strobes, six smoke detectors, sprinkler flow and tamper supervision, monitored by a UL-listed central station.

SECTION 31 23 00 — EXCAVATION AND FILL

Building pad excavation and backfill to the geotechnical report Terra-Tex 26-1188; 3,000 psf bearing; footings 24 inches minimum below finished grade; rock excavation paid under Unit Price No. 1. Site grading, paving and utilities beyond 5 feet of the building are by a separate contract.