



101 LOBBY
500 SF

102 CONFERENCE
500 SF

103 OFFICE
500 SF

104 OFFICE
500 SF

SK-1

105 BREAK ROOM
500 SF

108 OFFICE
500 SF

106 RESTROOM M
250 SF

WC-1 WC-1
107 RESTROOM W
250 SF

109 IT / STORAGE
500 SF

200 WAREHOUSE
8,000 SF

HB-1

TAG	DESCRIPTION	QTY
WC-1	WATER CLOSET, FLOOR MOUNT, 1.28 GPF	4
UR-1	URINAL, WALL HUNG, 0.125 GPF	1
LAV-1	LAVATORY, WALL HUNG	4
SK-1	BREAK ROOM SINK, DOUBLE BOWL	1
MS-1	MOP SINK	1
EW-1	ELECTRIC WATER COOLER, BI-LEVEL	1
WH-1	ELECTRIC WATER HEATER, 40 GAL	1
HB-1	HOSE BIBB	4



AREA	HAZARD	SF/HEAD	HEADS
OFFICE 4,000 SF	LIGHT	200	20
WAREHOUSE 8,000 SF	ORDINARY GRP 2	130	62

1. DOMESTIC WATER: 2" SERVICE WITH RPZ BACKFLOW; COPPER TYPE L ABOVE GRADE, PEX-A PERMITTED IN WALLS.
2. SANITARY: PVC SCH 40 UNDERGROUND, CAST IRON ABOVE GRADE; APPROX. 420 LF TOTAL.
3. GAS: 1-1/2" TO UH-1/UH-2 AND 3/4" TO WH-1; METER BY UTILITY.
4. ROOF DRAINS (4) AND OVERFLOWS (4) WITH 6" LEADERS TO STORM; SEE CIVIL FOR SITE STORM.
5. SPRINKLER: WET PIPE, 6" RISER, FDC AT NORTH WALL; FLOW TEST 09/2026 TO BE PROVIDED BY OWNER.

BLACKLAND COMMERCIAL BUILDERS (SYNTHETIC C)
PRAIRIE CREEK OFFICE/WAREHOUSE — BUILDING 2

SHEET TITLE

PLUMBING PLAN & FIXTURE SCHEDULE

SCALE: 1/8" = 1'-0" DATE: 09/12/2026

REV: 2 ADDENDUM 1: 09/19/2026

SHEET NUMBER

P-101